

ADDENDUM NO. 01

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

Replace 6 Gates & Controllers, Fulton Reception Diagnostic Correctional Center
Fulton, MO
PROJECT NO. C1918-01

Bid Opening Date: 1:30 PM, Thursday, March 3, 2022 (Not Changed)

Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. Section 00116 – INVITATION TO BID:

- a. Revise paragraph 4.0.A to remove proposals for “Design Services”

The project includes ~~Design services to~~ the replacement of six (6) existing gates, controllers, and associated wiring at Fulton Reception and Diagnostic Center (FRDC).

2. Section 011000 – SUMMARY OF WORK

- a. Add subparagraph 1.5.C.1.a to read:

Provide the Department of Corrections (DOC) 24 hour notice prior to having any aerial equipment such as a man basket lift on the gate 13 closed side area so that DOC staff can prepare for and coordinate the de-energizing of the lethal fence for safety.

3. Section 323113.34 CHAIN DRIVEN SLIDING GATE OPERATORS FOR CORRECTIONAL FACILITIES (GATE 13):

- a. *Revise paragraph 2.1.E to read as follows and eliminate subparagraphs 2.1.E.1-3:*

E: Motor Housing and Chain tube: Reuse existing.

DRAWING CHANGES:

1. Drawing A206:

- a. Revise Keynote 01 to read:

CHAIN DRIVEN OPERATOR AND ENCLOSURE - RETAIN ENCLOSURE AND REMOVE AND SALVAGE OPERATOR TO OWNER. INSTALL NEW CHAIN DRIVEN OPERATOR.

- b. Revise Keynote 07 to read:

CHAIN TUBE - RETAIN TUBE AND REMOVE AND REPLACE CHAIN

COMPONENETS

2. Drawing E1.1:

- a. Revise note 1 and 2 to change the word "CONTROLLER" to "OPERATOR".
- b. Keynote 2: Remove last sentence (PAINT STEEL BASES ON GATES 3, 4, AND 13).
- c. At Gate 13, add keynote 3 to read:

REPAIR EXISTING CONTROL CONDUIT FROM BOTTOM OF MOTOR OPERATOR
INTO THE GROUND

GENERAL:

1. Copy of the Pre-Bid meeting Attendance Record is attached for information only. Changes to, or clarification of, the Bid Documents are only made as issued in the Addenda.

END ADDENDUM NO. 01